Commissioning GFCH-1 Part number: 8044339





General operating condition

Data sheet

Feature	Value
Design	Single-axis system
Scope of action	Activation of the axes in test mode Data backup and documentation Instruction of machine operators, e.g. in error diagnostics and eliminating errors or in changing the position values Configuration and parameterisation of the axes Optimisation of control parameters and homing Checking of wiring, connections, travel paths and energy chains
Work involved on site	3 working hours
Customer requirements	Use of Festo components Access to the machine or system Mechanical, pneumatic and electrical work is completed Qualified personnel responsible for the machine must be present on the agreed date
Provision of services	8-10 days subject to agreement